

incorporate new information or deviations from the assumptions and projections.

8) Plan future projects using the typical time frames listed in Table 10.

Table 10 – Recommended Typical Schedule for Water System Projects (Months)

Project Type	Preliminary Design	Land Acquisition	Final Design	Construction¹	Total Duration
Transmission Pipeline	3	9	3	8 ¹	23
Tank or Pump Station	3	12	3	18 ¹	36
Multi-jurisdictional	24	12	12	24 ²	72

Notes:

1. Includes 60 days for advertising and contract review.
2. Includes 90 days for advertising and contract review.